

CONSTRUCTION NOTES

THE FOLLOWING WORK SHALL BE COMPLETED PRIOR TO LIFT INSTALLATION PROCEDURE. ENSURE THE BUILDING FABRIC CAN WITHSTAND THE LOADS AS SHOWN.

WORKS BY OTHERS

- Form a load bearing pit to the dimensions shown. If the lift is external make provisions to prevent standing
- Provide a plumb foot print for the lift to the dimensions shown.
- Provide a fixing point at the upper threshold for the lift fixings. Push pull load 100kg. 3.
- 4. Provide a dedicated SP&N supply terminated in a lockable isolator as shown at the lower level.
- Dedicated analogue telephone line adjacent to the isolator.
- Provide a 100 diameter duct or trunking from the control cubicle in to the long side of the lift at the lower 6. evel
- 7. Clear access to the installation area.
- Assistance with offloading and distribution of the lift equipment.
- Storage area close to the lift installation.
- 10 Fall protection at the upper levels.
- 11. Clear working area for installation
- 12. Welfare facilities.
- 110v power for tooling. 13.
- 230v external rated twin socket outlet close to the lift for future maintenance operations.
- 50lux illumination at both levels for code compliance.
- 200lux illumination at floor level in front of the control cubicle. 16
- 1500 turning circle at both levels for disabled access.

TECHNICAL SPECIFICATION

CONTRACT LOAD 400Ka PLATFORM SPEED IF TRAVEL EXCEEDS 1400mm 0.1m/s CONTROL SYSTEM VOLTAGE 24v POWER SUPPLY 240v 13A

ELECTRICAL DATA

0.55kW STARTING CURRENT 18A RUNNING CURRENT 4.5A

FINISHES

Lift Enclosure TBA at contract stage Doors and Frames TBA at contract stage BS 22 B 15 Pearl Gray 3. Control Box


Standard Anthracite (contrast for compliance) Carriage Centre Covers 5. Carriage Side Panels Standard Pearl (contrast for compliance)

Carriage Floor Black Studded Rubber


CONTROL CABINET INFORMATION

OUR CONTROL CABINET WILL BE A WEATHER PROOF CONSTRUCTION TO IP65 STANDARD AND SHALL BE MOUNTED IN A SUITABLE POSITION NOT MORE THAN 5Mtrs FROM THE GUIDE BASE PLATE. BUILDER TO INSTALL A PLASTIC DUCT 100 X 100 FROM THE CUBICLE TO THE LIFT SHAFT AREA. THERE SHALL BE ADEQUATE LIGHTING AND ACCESS TO THE CONTROL CABINET FOR MAINTENANCE AND **EMERGENCY PROCEDURES TO BE CARRIED OUT**

WEIGHT: 90 - 140 Ka's




ENCLOSURE LOADING DIAGRAM



DENOTES THE POINT AT WHICH THE HYDRAULIC RAM


THE OVERALL ENCLOSURE WEIGHT IS DEPENDANT ON THE FLOOR TO FLOOR TRAVEL DIMENSION.

THE ENCLOSURE LOADING DIAGRAM IS SHOWN FOR INFORMAL PURPOSES ONLY, AND IS BASED ON A LIFT OF 6000mm FFL / FFL AND AN ENCLOSURE WEIGHT OF 1750kgs.



Base Dimensions and Guide Frame Drillings

NICHE LIFTS LTD Office 15 & 16, 12 Farwig Lane, Bromley, Kent. BR1 3RB Tel: 020 8295 2852 Fax: 020 8466
e-mail: contracts@nichelifts.com Web Site: www.nichelifts.com



LIFT THRESHOLD FIXING DETAIL

Issued for information only

BY	DATE	ISSUE	MODIFICATION	CHECKED

Hydraulic Platform Lift Standard Layout & Builders Work 1400 x 1100 Platform Through Car with Upper Gate

NICHE LIFTS Ltd	DRAWN BY	DATE	CHECKED	SCALE
NICHE LIFTS LIG	TMP	07.12.18		NTS
Do not scale this drawing. All dimensions	DRAWING NUMBER			
in millimetres		210	3/1	
1695	Sh)
1695	Sheet 2 of 2			<u>.</u>